

## KENNEBUNK LIGHT & POWER DISTRICT SINGLE PHASE PRIMARY UNDERGROUND DISTRIBUTION

CUSTOMER TO PROVIDE PLOT PLAN APPROVED BY THE APPROPRIATE TOWN AND REGISTERED AT THE YORK COUNTY REGISTER OF DEEDS.

POLE AND PAD LOCATIONS TO BE DETERMINED BY K.L.P.D.

CONDUIT LOCATION AND SIZE TO BE DETERMINED BY K.L.P.D.

NO MATERIALS WILL BE ORDERED UNTIL "ELECTRIC SERVICE APPLICATION", "AGREEMENT" FORM (IF REQUIRED), "EASEMENT" FORM (IF REQUIRED) AND ANY "ADVANCE FOR CONSTRUCTION" (IF REQUIRED) HAVE BEEN RECEIVED BY K.L.P.D.

- 1 CONDUIT TERMINATOR - SUPPLIED BY K.L.P.D.
- 2 GROUNDING CLAMP - SUPPLIED BY K.L.P.D.
- 3 TEN FEET OF 2 INCH STEEL GALVANIZED CONDUIT AND 20 TO 30 FEET OF 2 INCH SCHEDULE 40 PVC CONDUIT TO BE SUPPLIED BY K.L.P.D.  
TWO CONDUITS, GROUNDING CLAMPS AND TERMINATORS MAY BE REQUIRED.
- 4 FOUR STANDOFF BRACKETS WITH 2 INCH CLIPS.
- 5 PLASTIC 2 INCH CONDUIT BUSHING - SUPPLIED BY K.L.P.D.
- 6 CONDUIT - 2 1/2" SCHEDULE 40 PVC. TO BE SET AT A DEPTH OF 24 TO 30 INCHES.  
BACKFILL TO BE CLEAN SAND AND WITH NO BUILDING DEBRIS.  
CONDUIT TO END 3 FEET FROM UTILITY POLE.  
PULL ROPE TO BE INSTALLED IN CONDUIT.  
TRENCH TO BE LEFT OPEN AT POLE WITH NO DEBRIS IN TRENCH.  
SCREENED SAND PILE TO BE LEFT AT POLE.  
ONE FOOT OF SAND TO BE LAID BELOW AND ABOVE URD CABLE AT THE TIME THE UNDERGROUND CABLE IS INSTALLED BY K.L.P.D.
- 7 FIBERGLASS PAD TO BE PROVIDED BY K.L.P.D. AND INSTALLED BY CUSTOMER.
- 8 PRIMARY URD CABLE - SUPPLIED AND INSTALLED BY K.L.P.D.
- 9 CAUTION TAPE TO BE INSTALLED 6 INCHES BELOW FINISHED GRADE.

